FOR CONSULTATION

KEY

- PROPOSED CYCLEWAY & FOOTWAY RESURFACING (RED ASPHALT)
- PROPOSED CYCLEWAY & FOOTWAY RECONSTRUCTION (FLEXIBLE CONSTRUCTION)
- PROPOSED KNEE HIGH TIMBER RAILING
- PROPOSED TACTILE PAVING FOR CROSSING
- PROPOSED CYCLEWAY PAVING
- PROPOSED LED HALO BELISHA BEACON
- EXISTING STREET LIGHTING COLUMN
- PROPOSED REMOVABLE/LOCKABLE BOLLARDS
- PROPOSED PCC EDGINGS
- PROPOSED PCC KERBS
- PROPOSED POST & SIGN PLATES
- TOPSOIL & SEED

NOTE.

VARIOUS STREET FURNITURE REPAIRS & RELOCATION WILL BE UNDERTAKEN
ALL ROAD MARKINGS WILL BE REFRESHED

HAYDON ROAD

ROSE AVENUE

KEEP CLEAR

Proposed Timber knee high railing

Proposed Crossing widened to include Cycles

Proposed Road Markings refreshed

Proposed Sign PS05

Proposed Cycleway/Footway reconstructed to new alignment

Proposed Timber knee high railing

Proposed new LED Halo Belisha Beacon

Proposed new LED Halo Belisha Beacon

Proposed Sign PS04

Proposed new High Friction Surfacing and "SLOW" Road Marking

Proposed Timber knee high railing

Proposed Crossing widened to include Cycles

Proposed Cycleway tactile Paving

Proposed Cycleway/Footway resurfacing Red Asphalt

SLOW

Aylesbury Services

Reproduced from the Ordnance Survey mapping with the permission of the Controller of His Majesty's Stationery Office © Crown Copyright. Unauthorised reproduction infringes Crown Copyright, and may lead to prosecution or civil proceedings.

Fenn & Fenn Ltd Licence No 329032

Client:-
Buckinghamshire Council
Transport Infrastructure & Delivery
Walton Street
Aylesbury
Buckinghamshire
HP20 1UY

Project:-
Haydon Road
Proposed Tiger Crossing
Consultation Plan
(Sheet 1 of 1)

Surveyed By:-	Drawn By:-	Checked By:-	Sheet Size	Date
DS	DRF	GS	A3	07/10/2026

Drg No:-	Rev:-	Scale:-
F&F/BC/26/97/C/2002	-	NTS

Proposed Sign PS03

Proposed Timber knee high railing

Proposed Cycleway & Footway resurfacing (red)

Proposed new Tactile Paving

Proposed Cycleway/Footway reconstructed to new levels

Proposed new LED Halo Belisha Beacon

Proposed new Bollards x5

Proposed carriageway resurfacing high skid resistance

Proposed Cycleway tactile Paving

Proposed new kerbs

Proposed Road Markings refreshed

Proposed Lane Markings adjusted

Proposed Lane Markings adjusted

Proposed carriageway resurfacing

Proposed new kerbs

Proposed new Cycle link from carriageway to cycleway

Proposed new LED Halo Belisha Beacon

Proposed footway/cycleway reconstructed to new levels

Proposed Raised Speed Table incorporating Pedestrian & Cycle Crossing

Proposed Sign PS02

Proposed Sign PS01

SLOW

BUS STOP

BICESTER ROAD

SERVICE ROAD

SAINSBURYS

FOR CONSULTATION

N

Grid North

KEY

- PROPOSED CYCLEWAY & FOOTWAY RESURFACING (RED ASPHALT)
- PROPOSED CYCLEWAY & FOOTWAY RECONSTRUCTION (FLEXIBLE CONSTRUCTION)
- PROPOSED KNEE HIGH TIMBER RAILING
- PROPOSED TACTILE PAVING FOR CROSSING
- PROPOSED CYCLEWAY PAVING
- PROPOSED LED HALO BELISHA BEACON
- EXISTING STREET LIGHTING COLUMN
- PROPOSED REMOVABLE/LOCKABLE BOLLARDS
- PROPOSED PCC EDGINGS
- PROPOSED PCC KERBS
- PROPOSED POST & SIGN PLATES
- TOPSOIL & SEED

NOTE.

VARIOUS STREET FURNITURE REPAIRS & RELOCATION WILL BE UNDERTAKEN
ALL ROAD MARKINGS WILL BE REFRESHED

Reproduced from the Ordnance Survey mapping with the permission of the Controller of His Majesty's Stationery Office © Crown Copyright. Unauthorised reproduction infringes Crown Copyright, and may lead to prosecution or civil proceedings.

Fenn & Fenn Ltd Licence No 329032

Client:-
Buckinghamshire Council
Transport Infrastructure & Delivery
Walton Street
Aylesbury
Buckinghamshire
HP20 1UY

Project:-
Bicester Road
Proposed Raised Table Tiger Crossing
Consultation Plan
(Sheet 1 of 1)

Surveyed By:-	Drawn By:-	Checked By:-	Sheet Size	Date
DS	DRF	GS	A3	07/10/2026

Drg No:-	Rev:-	Scale:-
F&F/BC/26/97/C/2001	-	NTS